



VARDHAMAN MAHAVEER OPEN UNIVERSITY, KOTA.

(Formerly : Kota Open University, Kota)

Rawatbhata Road, Kota

No. F-2/ VMOU/ G.Ad./ Tender/ 12/ 1233

Date : 17 /01/2012

Detail Tender Notice

Sealed tenders are hereby invited in the prescribed form, from contractors, duly approved in various state Govt. / Semi Govt. works departments, for following work –

S. No.	Description	Estimated Cost	Earnest Money	Tender Fees	Period
1.	Installation of Submersible pump a/w accessories.	1.50 lac	3000/-	100/-	15 Days

Earnest money either in cash or in form of D.D in favour of “**Vardhaman Mahaveer Open University, Kota**” should be deposited along with tender form. Tender forms may be downloaded from our website or may be obtained in cash from this office during the working hours from **20 /01/2012 to 28 /01 /2012**. Tenderers who downloaded tender form must enclose a pay order or D.D. of Rs. 100/- in favour of as above with tenders against the tender form fees. Sealed tender shall be received in this office on **30 /01/2012 up to 2:00 P.M** & shall be opened on same day at **3:00 P.M**. Conditional tenders & tenders received without Earnest money will not be considered & shall be rejected. The University have the rights to accept or reject any tender without assigning any reason.

REGISTRAR

Copy to :

1. Section Officer, A&F, VMOU, Kota.
2. All Notice Board, VMOU, Kota.

Asstt. Registrar, G.Ad.

OFFICE OF THE REGISTRAR, VARDHAMAN MAHAVEER OPEN UNIVERSITY, KOTA.**Name of work :- Installation of Submersible pump a/w G.I. Pipe & sub. Cable****Estimated Cost :- Rs.1.50 lacs****Cost of Tender :- Rs. 100 /-****Earnest Money :- Rs. 3,000 /-****Completion period :- 15 days****Date of Sale :- 20/01/2012 to 28/01/2012****Date of Receiving :- 30/01/ 2012 up to 2.00 pm****Date of Opening :- 30/01/ 2012 at 3:00 pm****Issued to M/S _____****"PART- A" G-SCHEDULE**

No	Description	Qty.	Unit	Rate	Amount
1	Supply and installation of submersible motor pump sets ISI marked (IS:8034-1989) of approved make with required accessories including making connection suitable for T.W./D.C.B.Open well. The Job includes lowering of riser pipe. G.I./H.D.P.E. pipe with rope, cables, installation of complete fitting and accessories, jointing of electrical cables up to switch board. All labour for testing of submersible pumps set and supply of water to water mains, complete in all respect. 150 mm diameter submersible pump shall have following HP Rating, phase, Head, minimum Discharge respectively. 15.0 Hp, 3- ϕ , (90-125) Mtr. (400-167) LPM KSB/Kirlosker/Calama.	1	Each	42000.00	42000.00
2	Providing and lowering of G.I. Pipes, flange pipe including rubber washer and nuts of 8 mm dia complete in all respect ISI Make. B Class 75 mm dia	65	R. Mtr.	385.00	25025.00
3	P/Laying ISI marked P.V.C. insulated submersible cable conforming to IS: 694 with flexible copper conductor including making connection etc. as required - Finolex/Havell's/ Rallison/National. 6.0 Sq.mm 3 core flat	320	R. Mtr.	79.60	25472.00
4	Unlowering of submersible pump set with all piping from a tube well / open well complete (Labour charge only) including transportation of tripod, chain, pulley block and other materials required and lowering of repaired / new pump in the tube well/ open well complete in all respect	2	Each Job	3500.00	7000.00
Total Rs.					99497.00
					0

I / We here by agree to execute the above work at the following rate.

Rate are % above / below **(in words)** on "G" SCHEDULE

Rate are % above / below **(in Figures)** on "G" SCHEDULE

Signature of Contractor with seal

PART "B" H - SHEDULE

No	Description	Qty.	Unit	Rate (to be quoted by the contractor)	Amount
1	Supply, Installation & connection of cubical pannel of 14 S.W.G. iron sheet as desired. It should be factory made, vermin proof, lockable & duly painted. The pannel should consists including cost of as follows :- Cubic pannel type 100 Amp. TP&N main Switch (make L&T) including HRC fuses. Star-Delta starter, (Crompton/L&T/Seimens make) suitable for above motor. Single phase preventer devices 440 Volt suitable for above motor pump set. Ampere meter 0-60 Amp. range (I.S.I. make). R-Y-B phase including lamps with toggle Switches. MCB TP & N of 63 Amp. Category I (Indo Kopp/ Standard/ Geco/ Havells) Necessary cable glands & wiring of panel with suitable size copper conductor. PVC insulated wires with necessary clips etc.	01	Nos.		

Signature of Contractor with seal

Terms & Conditions :-

- 1- Conditional Tender shall not be accepted.
- 2- The Rates of Part of "A" G-Shedule are based on P.W.D. B.S.R. 2010 w.e.f. Oct. 2010 & Electrical BSR w.e.f. 01/12/06.
- 3- In case of any typographical error or mistake in print the above B.S.R's shall be binding and final.

**Asstt. Registrar, G.Ad.
VMOU, KOTA**